

MONROE MUNICIPAL UTILITIES AUTHORITY

**PROJECT:** REHABILITATING WELL 11

**ORIGINAL BID PRICE:** \$133,970.00

**NATURE OF WORK OF ORIGINAL BID:** Rehabilitate Well 11 at the Corkery Lane Station. Restore specific capacity from 6 to 15 gallons per minute per foot (gpm/ft). Install new pump in Well #11. Restore site to original condition.

**CHANGE ORDER AMOUNT:** \$97,195.00

**ADDITIONAL WORK:** It was determined that a New Pump Design was necessary to provide 300HP vertical hollow shaft motor, (510) feet of 10" x 1-15/16" column assembly, and bowl assembly rated for 1500 gpm against 616' TDH.